



## 8800 Series Submittal Data

**JOB NAME:** \_\_\_\_\_

**LOCATION:** \_\_\_\_\_

**ARCH/ENGR:** \_\_\_\_\_

**CONTRACTOR:** \_\_\_\_\_

**MODEL NO:** \_\_\_\_\_

**TYPE GAS:** \_\_\_\_\_

**BTU INPUT/OUTPUT:** \_\_\_\_\_

### ADDITIONAL INFORMATION:

#### Standard Features

- 82% Efficiency
- Bronze Headers
- Structural Steel Frame
- Front Mount 24V Controls
- Victaulic Connections
- On/Off Firing
- Field Reversible Headers
- 2-Pass Finned Copper Tube Heat Exchanger
- Slide Out Heat Exchanger
- Slide Out Burner Tray
- ASME Pressure Relief Valve Mounted
- 2 ½" Interlocking Combustion Chamber
- Integral Drafthood
- Thermometer
- Temperature/Pressure Gauge
- 115/24V Transformer
- Indoor Installation
- Flow Switch Mounted and Wired
- IID, Spark Ignition Control
- Manual Reset High Limit
- Operating Aquastat
- Leak Test Valves
- CSD-1 Gas Train Compliant
- High/Low Gas Pressure Switch (2800 – 4000)
- Additional High Limit (2800 – 4000)
- Additional Safety Valve (2800 – 4000)
- Dual Flue (3200 – 4000)

#### Optional Equipment

- 2 Stage Firing
- 4 Stage Firing (Spark Ignition Only)
- Propane Gas
- Cupronickel Heat Exchanger
- Wired & Mounted Flange
- Alarm Bell
- Flame Failure Dry Contact
- Main Flame Status Contact
- Enable/Disable Relay 24V
- Enable/Disable Relay 120V
- Low Gas Pressure Switch
- High Gas Pressure Switch
- Left Hand Gas Connection
- Right Hand Water Connection
- Single Plenum Flue (3200 – 4000)
- Dual Flue (2000 – 2800)
- Power Venter Wiring
- 1PH Phase Pump Contactor
- 3PH Pump Contactor (shipped loose)
- Light Package
- Remote/Local Switch
- Sidewall Vent Kit
- Vent Termination Hood
- Pump

#### Gas Trains

- CSD-1 Code
- Kentucky Code
- FM Code